

Public Works Department
305 West Third Street, East Wing, Third Floor
Oxnard, California 93030
Tel 805.385.8280



May 6, 2019

ADDENDUM NO. 2

**THIN MAINTENANCE OVERLAY PROJECT PHASE II
SPECIFICATION NO. PW 18-58**

SCHEDULED BID OPENING DATE: MAY 20, 2019

TO ALL BIDDERS OF RECORD:

Acknowledge receipt of this addendum by enclosing one signed copy with your bid documents. Failure to do so may subject bidder to disqualification. This addendum consists of two (2) pages. This addendum forms a part of the bid documents as follows:

1. Page SP 46 of the Special Provisions has been revised. Bidders are to replace the existing SP 46 with the attached Revised SP 46. The revisions are shown in red for convenience.

Addendum No. 2 Received: Date: _____

Contractor's Name

Address

Authorized Signature

City State Zip Code

Name and Title

Telephone Number, Including Area Code

excavating and furnishing and placing concrete footings, connecting new fences to existing fence, and any other related work shall be considered as included in the Contract lump sum price and no additional compensation will be made therefore.

1500 TRAFFIC

1505 TRAFFIC CONTROL AND PUBLIC CONVENIENCE AND SAFETY
(Bid Item)

1505-1 SCOPE

The Contractor shall provide, for the protection of the public, all necessary barricades, traffic cones, warning signs, flagmen, lights, and other safety devices in accordance with Section 12-3 of the SSS and the current requirements set forth in the MUTCD.

Contractor shall furnish, install, and maintain a trailer mounted, solar powered portable changeable message sign upon which varying electronically generated messages will be displayed to traffic, as specified in Section 7-10.6.3 of the General Provisions.

Portable CMS shall be installed in the beginning and end of each segment of arterial road to be constructed.

Refer to SSS and/or MUTCD Guidelines for the use of portable changeable message signs in work zones.

Contractor shall also provide traffic control for the safety of survey crew working on this Project.

Additionally, the Contractor shall install temporary railing (type K) between any lanes carrying public traffic and any excavation, obstacle, or storage area when any of the following conditions exist:

1. Excavations: any excavation the near edge of which is 12 feet or less from the edge of the lane, except for any of the following:
 - a. Excavations covered with steel sheets or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
 - b. Excavations less than one foot deep.
 - c. Trenches less than one foot wide for irrigation pipe or electrical conduit or excavations less than one foot in diameter.
 - d. Excavations parallel to the lane for the purpose of pavement widening or reconstruction that are less than one foot deep.
 - e. Excavations in side slopes, where the slope is flatter than 4:1.
 - f. Excavations protected by existing barrier or railing.
2. Temporarily unprotected permanent obstacles including but not limited to the following options:
 - a. Whenever the Work includes the installation of a fixed obstacle together with a protective system, such as a sign structure with a protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or
 - b. Whenever the Contractor, for its convenience and with permission of