

Public Works Department
305 West Third Street, East Wing, Third Floor
Oxnard, California 93030
Tel 805.385.8280



September 10, 2019

ADDENDUM NO. 1

**ROUTE 23 BUS STOP INSTALLATION PROJECT
SPECIFICATION NO. PW 19-81**

SCHEDULED BID OPENING DATE: September 17, 2019

TO ALL BIDDERS OF RECORD:

Acknowledge receipt of this addendum by enclosing one signed copy with your bid documents. Failure to do so may subject bidder to disqualification. This addendum consists of this one (1) page and two (2) pages of attachments and forms a part of the bid documents as follows:

1. **The Special Provisions have been revised.** Bidders are to include the attached page SP64A into the Contract Documents. This page includes new section 1903 CONCRETE BOLLARD.
2. **The Bid Packet has been revised.** Bidders are to replace page B4 provided with the Contract Documents with the attached Revised B4.

Addendum No. 1 Received:

Date: _____

Contractor's Name

Address

Authorized Signature

City State Zip Code

Name and Title

Telephone Number, Including Area Code

1903 CONCRETE BOLLARD

1903-1 SCOPE OF WORK

The scope of the Work shall consist of installing round concrete bollard anchored at the north end of the concrete boarding island on Bus Stop #20 per the Engineer's direction.

1903-2 MATERIALS

Dimensions: 24" diameter x 36" height (max.), with 1" tall x 1/2" deep reveal 6" down from top.

Weight: 440 lbs per 1' length

Materials: 3/8" steel rebar, Concrete for bollard shall conform to Section 201 of the Standard Specifications and shall be Class 500-C-2500.

Stress Load: Not less than 4,500 PSI at 28 days

Finish : Medium sandblast

Color: Brown

1903-3 CONSTRUCTION

The concrete bollard shall be reinforced with rebar to ensure maximum strength and durability. Bollard shall be installed vertically square, with an above grade height of 36 inches. Bollard shall be anchored in concrete pad with a protruding 3" galvanized pipe.

1903-4 PAYMENT

Installation of concrete bollards shall be paid on a unit cost basis as shown in the Bid Sheet. Such payment shall be considered full compensation for furnishing all labor, materials, equipment, and incidentals necessary to complete the Work in accordance with these specifications.

18	Remove Pavement Striping And Marking	1515-4	SF	320	
19	Paint Curb Red (2 Coat)	1515-4	LF	1,350	
20	Install Detail 22 - Thermoplastic	1515-4	LF	100	
21	Install Detail 38 - Thermoplastic	1515-4	LF	400	
22	Install Detail 40 - Thermoplastic	1515-4	LF	100	
23	12" Solid White - Thermoplastic	1515-4	LF	1,250	
24	Install "STOP" Pavement Marking - Thermoplastic	1515-4	EA	2	
25	Install "BUS ONLY" Pavement Marking - Thermoplastic	1515-4	EA	1	
26	Install Type VII (R) Arrow Pavement Marking - Thermoplastic	1515-4	EA	1	
27	Relocate Pedestrian Traffic Signal Push Button, Complete-In-Place	1520-23	EA	1	
28	Install Rectangular Rapid Flashing Beacon, Complete-In-Place	1520-23	LS	1	
29	Relocate Traffic Signal Pole And All Attachments	1520-23	LS	1	
30	Relocate Traffic Pull Box, Complete-In-Place	1525-4	EA	2	
31	Install R1-5 Sign And Post	1530-4	EA	2	
32	Furnish And Install Bus Stop Sign And Post	1530-4	EA	15	
33	Relocate Traffic Sign And Post, Complete-In-Place	1530-4	EA	1	
34	Furnish And Install "Right Turn Bus Exempt" Sign And Post	1530-4	EA	2	
35	Furnish And Install Bus Shelter With Solar Powered Led Lighting System, Complete-In-Place	1901-4	EA	2	
36	Furnish And Install Bench	1901-4	EA	2	
37	Furnish And Install Trash Bin	1901-4	EA	2	
38	Furnish And Install Bike Rack	1901-4	EA	2	
39	Furnish And Install Pedestrian Guard Rail	1902-4	LF	245	
40	Install 24" Dia. X 36"H Round Concrete Security Bollard	1903-4	EA	1	
BASE AMOUNT TOTAL				\$	

Note: Several items may be adjusted or deleted. Any changes to the quantities for these items shall not classify as a substantial change as stipulated in Greenbook Section 3-2.2.1. Regardless of total actual volume compared to estimated quantities, the unit prices provided above shall be applied to the final quantity when payment is calculated for these items. No adjustment in the unit prices will be allowed. The City reserves the right to not use any of the estimated quantities, and if this right is exercised, the Contractor will not be entitled to any additional compensation. The cost of all labor, materials, export of