

This is a tabulation of bids results and not an offer of award or contract  
The City reserves the right to reject all bids

**PROJECT NAME: Neighborhood Street Resurfacing - Kamala Park And Bartolo Square South**

<b>Specification No.</b>	<b>PW 23-104</b>	<b>TORO ENTERPRISES, INC.</b>
<b>Owner:</b>	<b>City of Oxnard</b>	2101 E. Ventura Bl Oxnard, CA 93036
<b>Bid Opening Date:</b>	<b>6/28/023</b>	#1

ITEM NO.	DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE	EXTENDED AMOUNT
1	Mobilization/Demobilization (not to exceed 5% of the Total Bid Price)	LS	1	\$150,000.00	\$150,000.00
2	Traffic Control And Public Convenience And Safety	LS	1	\$495,000.00	\$495,000.00
3	Storm Water Pollution Prevention Plan	LS	1	\$22,000.00	\$22,000.00
4	Cold Mill AC Pavement (2" Max.)	SQYD	23,884	\$4.20	\$100,312.80
5	Unclassified Excavation	CY	102	\$120.00	\$12,240.00
6	Class 2 Aggregate Base	TON	85	\$115.00	\$9,775.00
7	Asphalt Concrete, Type III (DGAC-B2 PG 64-10)	TON	100	\$254.00	\$25,400.00
8	Asphalt Concrete, Type III (DGAC-C2 PG 64-10)	TON	326	\$182.00	\$59,332.00
9	Asphalt Concrete, Type III (DGAC-D2 PG 64-10)	TON	1,185	\$200.00	\$237,000.00
10	Asphalt Rubber Aggregate Membrane (ARAM)	SQYD	38,400	\$5.36	\$205,824.00
11	Asphalt Rubber Hot Mix (ARHM-GG-C PG 64-16)	TON	4,970	\$150.00	\$745,500.00
12	Crack Seal	LB	10,200	\$5.65	\$57,630.00
13	Micro-Surfacing	TON	1,032	\$485.00	\$500,520.00
14	Remove And Replace PCC Sidewalk, 4" Thick	SQFT	3,200	\$15.00	\$48,000.00
15	Remove And Replace PCC Commercial Driveway, 8" Thick	SQFT	1,355	\$43.50	\$58,942.50
16	Remove And Replace PCC Residential Driveway, 6" Thick	SQFT	1,800	\$39.00	\$70,200.00
17	Remove And Replace PCC Cross Gutter And Spandrel	SQFT	4,006	\$40.00	\$160,240.00
18	Remove And Replace PCC Curb and Gutter (Type A2-6)	LF	1,220	\$141.00	\$172,020.00
19	Remove And Replace PCC Rolled Curb and Gutter Per Page 2, Appendix C	LF	200	\$146.00	\$29,200.00
20	Remove And Replace PCC Curb Ramp With Detectable Warning Surface Tiles, 4" Thick	SQFT	1,850	\$24.00	\$44,400.00
21	Install 24" Root Barrier Panel	LF	40	\$101.00	\$4,040.00
22	Adjust Water Valve Frame And Cover To Finished Grade	EA	63	\$1,185.00	\$74,655.00
23	Adjust Manhole Frame And Cover To Finished Grade	EA	32	\$1,005.00	\$32,160.00

ITEM NO.	DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE	EXTENDED AMOUNT
24	Adjust Survey Monument Frame and Cover To Finished Grade	EA	3	\$1,500.00	\$4,500.00
25	Install Pavement Markings in Thermoplastic	SQFT	5,113	\$6.55	\$33,490.15
26	Install Detail 2 In Thermoplastic	LF	1,890	\$0.71	\$1,341.90
27	Install Detail 22 In Thermoplastic	LF	8,086	\$1.97	\$15,929.42
28	Install Detail 29 In Thermoplastic	LF	315	\$3.28 *	\$1,033.20
29	Install Detail 38 In Thermoplastic	LF	725	\$1.67	\$1,210.75
30	Install 3" Double White Solid Parking Stall Stripe In Thermoplastic	LF	630	\$7.86	\$4,951.80
31	Install Blue RPM	EA	108	\$8.15	\$880.20
32	Install Or Remove and Replace Street Name Sign	EA	90	\$232.00	\$20,880.00
33	Remove, Relocate, Or Re-Install Traffic Sign Per City Std Plate 204	EA	34	\$190.00	\$6,460.00
34	Install Or Remove and Replace Sign Post Per City Std Plate 203/204	EA	39	\$197.00	\$7,683.00
35	Furnish And Install Detectable Warning Surface Tiles	SQFT	1,248	\$45.00	\$56,160.00
36	Grind PCC Concrete	SQFT	100	\$62.00	\$6,200.00
<b>Total Bid Price:</b>					<b>\$3,475,111.72</b>

\* Unit Price Correction

<b>TORO ENTERPRISES, INC.</b>	
<b>Total Bid SUBMITTED</b>	<b>\$3,475,111.72</b>
<b>Total Bid VERIFIED</b>	<b>\$3,475,111.72</b>

<b>Subcontractors:</b>	Case Land Surveying (Surveying 2.7%)
	American Pavement Systems (ARAM 6.7%)
	Pavement Rehab Company (Crack Sealing 1.8%)
	American Asphalt South (Micro Surfacing 12.5%)